

CONTRACTOR'S PROPOSAL

Note: Bidders shall refer to plans, details, and materials schedules in drawings for exact bid item description and specifications. Any discrepancies in quantities or specification requirements must be submitted in writing to SPI / SSP prior to bid opening date.

PLANT SCHEDULE

COMMON NAME	SIZE	QUANTITY	UNIT COST	TOTAL
PALMS				
MED FAN PALM	B/B 60" (SINGLE TRUNK)	42		
SABAL PALM	B/B 8-10' TK. HT.	2		
WILD DATE	B/B 14-16' TK. HT.	1		
SHRUBS				
CROWN OF THORNS	5 GAL.	117		
LIROPE 'MAJESTIC'	3 GAL.	420		
GROUNDCOVERS				
HEARTS AND FLOWERS	4" POTS	351		
WEDELIA	4" POTS	1,170		
	Plant Schedule Subtotal \$			

MATERIAL SCHEDULE

MATERIALS	SIZE	QUANTITY	UNIT COST	TOTAL
GENERAL CONDITIONS/MISCELLANEOUS	L.S.	1	1	
DEMO/CLEANUP OF MEDIAN PLANTERS AND PRUNING OF PALMS AS PER PLANS	L.S.	1	1	
PREMIUM COMPOST - 2" LAYER (NINE KIDS COMPOST)	C.Y.	20		

SCREENED TOPSOIL - 8" LAYER FOR NEW PLANTING BEDS	C.Y.	100		
MULCH (HARDWOOD 2" MIN FOR ALL PLANTING BEDS AND WATERING BASINS - TEXAS NATIVES SHREDDED HARDWOOD MULCH)	BAGS (2 CF)	400		
HERBICIDE (ALL PLANTING AREAS AS SPECIFIED)	S.F.	3,650		
FERTILIZER (ALL PLANT MATERIAL PER DETAILS)	S.F.	3,650		
PLANTING TABLETS (PER DETAILS / AS SPECIFIED)	—	--		
PRE-EMERGENT (ALL PLANTING BED AREAS AS SPECIFIED)	S.F.	3,650		
POTTING MIX – MIRACLE-GRO ' MOISTURE CONTROL' (4 BAGS PER PLANTER)	BAGS (2 C.F.)	156		
GUYING/STAKING (ALL TREES / PALMS PER DETAILS)	EA	-		
FILTER FABRIC- 'FABRISCAPES' 4 OZ. NON-WOVEN FILTER FABRIC	S.F.	9,125		
WASHED GRAVEL – 6" LAYER OF 'MEDINA' 5/8" DECORATIVE GRAVEL.	C.Y.	160		
SMALL WEATHERED LIMESTONE BOULDERS (SIZE VARIES APPROX. 12X24X24")	EA	324		
CONCRETE CURB- 6 X 6" COLORED CONCRETE CURB (WITH # 3 RE-BAR AS PER PLANS/DETAILS)	L.F.	1,300		
CONCRETE PLANTER - PARK WAREHOUSE CONCRETE PEDESTAL PLANTER (SKU: 544pl280) 48" x 18" ROUND COLOR (A20 WHITE ACID WASH)	EA	39		
CONCRETE PAD - 6" X 3' X 3' COLORED CONCRETE PAD UNDER PLANTER (AS PER PLANS/DETAILS)	EA	39		
IRRIGATION SYSTEM - DEMO ADDITIONS/ADJUSTMENTS BY TEXAS LICENSED IRRIGATOR (ALLOWANCE)	ALLOWANCE	1	\$ 80,000	
MAINTENANCE (90 DAYS)	L.S.	1	1	
	Materials Schedule Subtotal \$			

ALTERNATE NO. 1	SIZE	QUANTITY	UNIT COST	TOTAL
REPAIR, RESET PAVERS (APPROX. 500 SF)	L.S.	1	1	

TOTAL \$ _____

CONTINGENCY (TOTAL X .05%) \$ _____

GRAND TOTAL \$ _____

ALTERNATE NO. 1 \$ _____

TOTAL number of calendar days to substantial completion (Max 90 calendar days) _____

BY: _____
Signature

Date

Printed Name

Title

COMPANY: _____

Address: _____

Phone: _____